

ALL 27 Poles to be mounted on concrete pedestals  
 2'-8" above grade, for a total mounting height of 32'-6".

Luminaire Schedule							Yield
Symbol	Qty	Label	Arrangement	Lumens	LLF	Description	Yield
	1	H	D160 ROTATED	82000	1.000	D160-AP1-150-PSM-V-CT-20	872
	12	P1	SINGLE	82000	1.000	D160-PP-150-PSM-V-CT-20	872
	1	G	D160	82000	1.000	D160-S-150-PSM-V-MT-CT-20	872
	1	W	SINGLE	82000	1.000	D160-W-400-MPH-E-16 MH	458

Total Yield = 28678

INITIAL FOOTCANDLE LEVELS AT 3' ABOVE GRADE.

Hourly Summary					
Label	Avg	Min	Max	Asphaln	Max Min
LOT	12.17	1.2	134	19.28	88.75